

1 **ME6243**

2 **Disassembly and Reuse of Demountable Modular Building Systems**

3 Yang Yang¹, Calvin Luk², Bowen Zheng³, Yifei Hu⁴, and Albert Ping-Chuen Chan⁵

4 ¹School of the Built Environment, Oxford Brookes University, Gypsy Lane, Headington, Oxford, U.K.
5 (corresponding author). Email: y.yang@brookes.ac.uk

6 ²Jockey Club Design Institute for Social Innovation, The Hong Kong Polytechnic University, Hung Hom,
7 Kowloon, Hong Kong S.A.R., China. Email: calvin.luk@polyu.edu.hk

8 ³Department of Building and Real Estate, The Hong Kong Polytechnic University, Hung Hom, Kowloon, Hong
9 Kong S.A.R., China. Email: bowen1999.zheng@connect.polyu.hk

10 ⁴Department of Civil and Environmental Engineering, The Hong Kong Polytechnic University, Hung Hom,
11 Kowloon, Hong Kong S.A.R., China. Email: yi-fei.hu@polyu.edu.hk

12 ⁵Department of Building and Real Estate, The Hong Kong Polytechnic University, Hung Hom, Kowloon, Hong
13 Kong S.A.R., China. Email: albert.chan@polyu.edu.hk

14

15 **Abstract**

16 Numerous efforts have been exerted to explore how modular building systems are built. But
17 limited research has focused on how modular building systems are deconstructed.
18 Deconstruction is a means to systematically disassemble buildings and prioritize building reuse.
19 This paper aims to understand the deconstruction process of modular building systems by
20 providing empirical insights into the disassembly and reuse processes. To achieve this goal,
21 this study employed a mixed-research method, incorporating ethnographic site observations,
22 semi-structured interviews, and archival research, through a case study of a four-story
23 demountable modular building. The empirical findings indicate that the disassembly process
24 consists of a hybrid sequential and parallel disassembly of modular units, while the reuse
25 process consists of four sub-processes: take-back, material tracking, quality inspection, and
26 touch-ups. The contribution of this study to the body of knowledge on deconstruction is twofold:
27 (1) Design for Deconstruction does not inherently ensure effortless ease of disassembly and (2)
28 factors such as client ownership, digital material tracking, and ease of value retention play

29 crucial roles in facilitating building reuse. These findings enhance the understanding of the
30 deconstruction process by addressing the gaps in procurement, information, and quality
31 between the disassembly (the first use cycle) and reuse phases (the second use cycle). By
32 exploring disassembly sequence, take-back mechanisms, technology-driven traceability, and
33 value retention processes, this paper provides valuable support to practitioners transitioning
34 towards the reuse of modular buildings.

35

36 **Practical Applications**

37 Disassembly and reuse of modular building systems has been practiced less frequently in the
38 construction sector. However, this practice will be in urgent demand given that the increased
39 temporary emergency facilities built around the world will end their service lives in the near
40 future. Consequently, it is essential to understand how modular buildings systems are
41 disassembled and reused, thereby providing valuable references for future deconstruction
42 projects. This research bridges this knowledge gap by providing insights into the issues and
43 facilitators associated with the disassembly and reuse processes of a real demountable modular
44 building. Firstly, the use of bolt and nut connection systems, as one of the Design for
45 Deconstruction principles, allows the separation of one module from another. However, it does
46 not automatically imply the effortless ease of disassembly, as potential lock-in stress of the
47 connections may be present. Secondly, the three facilitators, namely, retained building
48 ownership by the client, digitalized information tracking for individual modules, and ease of
49 repair and replacement of modular components, enable the successful relocation and reuse of
50 disassembled modules. Ultimately, these findings provide construction professionals with
51 useful guidance on better planning and managing the disassembly and reuse processes of
52 similar deconstruction projects in the future.

53

54 **Keywords:** deconstruction, disassembly, relocation, reuse, value retention process, circular
55 economy, Design for Deconstruction

56 **Introduction**

57 Modular construction has been increasingly adopted in response to crises (e.g., earthquakes,
58 pandemic) and the social needs of vulnerable populations (e.g., low-income groups, patients)
59 worldwide, owing to its fast on-site delivery. Examples include the modular construction of
60 hospitals, quarantine centers, and social housing (Chen et al. 2021; Tan et al. 2021; UNECE
61 2021; Ling 2023). More than 7,000 modular units were built for healthcare facilities in Wuhan,
62 Hong Kong, Shanghai, and Seoul (Construction Industry Council 2020). Moreover, hundreds
63 of prefabricated dwellings, designed to last between 5 to 10 years, were built in Germany and
64 Switzerland for migrants (UNECE 2021). However, if there is a lack of a thoughtful end-of-
65 life planning, most of these temporary modular buildings are likely to be scrapped once people
66 have recovered or transitioned to long-term housing. As a consequence, the disposal of these
67 buildings as demolition waste often results in a greater adverse environmental impact compared
68 to permanent housing (Seike et al. 2018). Therefore, it calls for the adoption of sustainable and
69 circular thinking when these temporary modular buildings are approaching their end-of-
70 services.

71 In the context of a circular economy (CE), deconstruction plays a crucial role in enhancing the
72 circularity of buildings, as it involves a thoughtful selective demolition of building components
73 (Pantini and Rigamonti 2020). Its primary objective is to maximize the reusability of building
74 parts and minimize demolition waste (Kibert 2003). By prioritizing the preservation of the
75 original physical properties and structural integrity of building parts, deconstruction ensures
76 the highest level of value retention and creation (Munaro et al. 2022). By adhering to the
77 principles of CE, deconstruction extends the lifespan of building components, making it a more

78 sustainable alternative to conventional demolition, where end-of-life construction materials are
79 typically treated as waste with minimal recovery effort.

80 Guidelines on deconstruction principles have been gradually established since the 1970s,
81 aiming to prolong the functional lifespan of buildings and enhance their reusability (Munaro et
82 al. 2022). Significant progress has been made in scientific research on deconstruction,
83 particularly in the fields of design for deconstruction principles (Ottenhaus et al. 2023; Munaro
84 and Tavares 2023; Munaro et al. 2022), methodologies for evaluating deconstructability of
85 buildings (Akinade et al. 2015; Basta et al. 2020; Kim and Kim 2023), and socio-technical
86 conditions for deconstruction (van den Berg et al. 2020). Various technical factors can affect
87 the extent to which a structure can be easily disassembled and reused, including the types of
88 materials used, the mechanisms of wet or dry joints, the methods of construction (on-site or
89 off-site) (Bertino et al. 2021), and quality of future reused elements (van den Berg et al. 2020).

90 Despite the existence of guidelines on deconstruction principles, only a small fraction, less than
91 1%, of buildings are completely demountable (Kanters 2018). This is primarily because
92 conventional design approaches do not prioritize ease of disassembly, leading to significant
93 damage to building components and limited potential for reuse once deconstructed. The
94 primary objective of deconstruction is to retain the majority of building parts in their current
95 state and minimize the amount of waste that needs to be recycled, downcycled or landfilled
96 (Akinade et al. 2017; Tatiya et al. 2018). The principle of deconstruction is commonly seen in
97 modular systems, such as mining camps, which are assembled for short-term use before being
98 relocated to the next site (O'Grady et al. 2021a). Similarly, temporary buildings constructed
99 using modular systems in response to emergency or crises, such as earthquakes or pandemics,
100 also adhere to this principle.

101 Modular building systems that incorporate dry connections can offer high potential for
102 deconstruction. These demountable connections facilitate relatively easy disassembly with
103 minimal damage to modular components, allowing them to retain their original shape or
104 functionality for future reuse (e.g., Sanchez and Haas 2018). A few studies have examined the
105 environmental benefits associated with the reuse of purpose-built modular structures (Minunno
106 et al. 2020; O’Grady et al. 2021a). While several modular building systems claim to be
107 relocatable and reusable, only a few modular buildings have been disassembled, reused, and
108 reinstalled in real-life (Ling 2023). Moreover, the understanding of the deconstruction
109 processes (including disassembly and reuse) in modular systems remains limited, because of
110 the scarcity and fragmented nature of existing studies on deconstruction of modular buildings
111 (Munaro et al. 2022). For instance, van den Berg et al. (2020) is one of the first studies that
112 revealed disassembly routines and documented repair work carried out for the disassembled
113 elements of a reversible modular building system. They further formulated several strategies
114 for increasing the likeliness of the demolition contractor taking a reuse/ recovery decision. It
115 implies that there are uncertainties associated with reuse and the reuse process has not been
116 widely practiced yet (van den Berg et al. 2020). Essentially, the dearth of research and practice
117 on deconstructing modular buildings stresses the need for in-depth investigation and
118 documentation to advance the deconstruction philosophies and improve the understanding of
119 deconstruction practices.

120 This paper aims to understand the deconstruction process of modular building systems.
121 Specifically, it seeks to provide empirical insights into the disassembly and reuse of
122 demountable modular buildings. By doing so, it contributes to the advancement of
123 deconstruction theories and the improvement of deconstruction practices. This research
124 represents a pioneering study that focuses on the deconstruction process of modular building
125 systems, offering two-fold novelty. Firstly, this paper fills in the knowledge gaps between the

126 processes of disassembly (the first use cycle) and reuse (the second use cycle) in modular
127 buildings, an area that has received limited attention in prior studies (Allam and Nik-Bakht
128 2023). Secondly, the empirical findings from the deconstruction process validate certain
129 Design for Deconstruction (DfD) principles by examining whether these principles facilitate
130 ease of disassembly. The insights gained from this study can generate new and valuable
131 knowledge in the fields of design and deconstruction of demountable modular buildings. The
132 understanding of the deconstruction process helps shape new practices, serving as a valuable
133 reference of global industry practitioners and policymakers seeking to comprehend the unique
134 considerations associated with deconstruction possibilities. Planners may also have the
135 opportunity to design with foresight, incorporating the deconstruction process into the initial
136 design stage and improving the ease of disassembly and reusability of modular buildings. The
137 improvement in the knowledge on deconstruction ultimately contributes to the transition into
138 a more circular and sustainable future for modular construction. The lessons learned from this
139 study may also generate fresh research ideas and directions for future advancements in
140 disassembling and reusing modular buildings.

141 The rest of this paper consists of five sections. The first section is a review of deconstruction
142 studies by addressing the critical knowledge gaps in the deconstruction process. Secondly, a
143 mixed-research method, incorporating ethnographic site observations, semi-structured
144 interviews, and archival research, through a case study, is described. Next, empirical findings
145 are presented by identify the key disassembly and reuse processes and sub-processes.
146 Subsequently, key lessons drawn from the findings are discussed, and theoretical and practical
147 implications are offered. Finally, the research novelty, limitations of the study, and future
148 research directions are highlighted.

149

150 **Literature Review**

151 Deconstruction aims to minimize demolition waste by systematic disassembling buildings to
152 maximize material reuse and recycling (Chini and Bruening 2002; Deniz et al. 2014; Mayer
153 2017). The deconstruction process primarily comprises disassembly and material recovery. On
154 the one hand, systematic disassembly allows buildings to be disconnected piece-by-piece
155 (Chini and Bruening 2002; Akinade et al. 2017) or layer-by-layer (Crowther 2005; Deniz et al.
156 2014). Achieving demountability relies on the adoption of DfD principles, such as modularity
157 and dry connections. On the other hand, the primary objective of deconstruction is to maximize
158 the potential for material recovery, including reuse and recycling (Akinade et al. 2017).
159 Building relocation and direct reuse of components and materials are preferable and more
160 sustainable compared to recycling, as they involve minimal reprocessing and downcycling
161 (Crowther 2001; Chini and Bruening 2002; Santos and de Brito 2007; Deniz et al. 2014;
162 Akinade et al. 2017; Allam and Nik-Bakht 2023). Importantly, building reuse represents great
163 challenges (Akinade et al. 2017), while empirical studies on this topic are lacking (O’Grady et
164 al. 2021b). Considering these aspects, the present study investigates the deconstruction process
165 through the lens of disassembly and reuse.

166

167 ***Disassembly Process***

168 The theory of time-related building layers (Brand 1994) emphasizes that a building should not
169 be seen as a single entity but rather a collection of separable layers, each with its own service
170 life, ultimately allowing for the separation of these layers into packages with similar life spans
171 (Crowther 2001). The six primary building layers are stuff, space, services, skin, structure, and
172 site. Consequently, a layer-by-layer approach is commonly employed when dismantling a
173 building. For instance, Mayer (2017) documented the disassembly process of a university
174 facility by removing building skin components, structural elements, and subassemblies in a

175 sequential manner. Santos and de Brito (2007) recorded the disassembly process of a two-story
176 building, starting with the removal of building systems and interior finishing materials,
177 followed by the dismantling of the external envelope, main structure, and foundations.
178 Similarly, van den Berg et al. (2020) described the disassembly process of a temporary nursing
179 home, which involved the gradual removal of interior finishes, fixtures, architectural features,
180 and finally, the disassembly of the framing and removal of the foundation (Denhart 2010). This
181 sequential approach, also known as linear or dependent disassembly, involves removing one
182 part at a time (Sanchez and Haas 2018; Deniz and Dogan 2014). It is adopted because a part
183 can only be disassembled once its connected parts have been disassembled (Sanchez and Haas
184 2018). In contrast, parallel or independent disassembly is employed when multiple parts can
185 be removed simultaneously due to their independent geometric relationships (Sanchez and
186 Haas 2018; Deniz and Dogan 2014). In determining the disassembly sequence, the geometric
187 relationship and interdependence between a part and its neighboring parts should be taken into
188 consideration (Sanchez and Haas 2018).

189 The complexity of the disassembly process can be influenced by various factors, such as types
190 and accessibility of connections (van den Berg et al. 2020). Modular building systems,
191 particularly those with demountable and accessible connections, have been recognized as an
192 ideal solution for efficient disassembly and reuse (O'Grady et al. 2021a). Connections using
193 welded joints or in-grout techniques often require destructive disassembly and consequently
194 result in increased damage and decreased reusability. In contrast, dry connections, such as
195 bolted and rivetted joints, facilitate the disassembly of volumetric modules as a whole,
196 minimizing the separation of different building parts and increasing their reusability. Moreover,
197 the accessibility of connections allows laborers to easily reach and utilize hand tools during the
198 disassembly process (O'Grady et al. 2021a; van den Berg et al. 2020). Skilled workmanship

199 and specialized tools can thus provide technical assistance in efficiently disassembling and
200 separating structures into reversible and irreversible component (van den Berg et al. 2020).

201 Although numerous DfD studies offer a range of dos and don'ts design principles, there is a
202 scarcity of empirical research documenting the integration of these principles into the actual
203 deconstruction process (O'Grady et al. 2021b). While it is widely acknowledged that modular
204 design, lightweight materials, and dry connections facilitate the ease of disassembly for
205 building components, the extent of this ease remains largely unexplored. To shed light on this
206 matter, further exploration is needed to understand the specific deconstruction process
207 employed for demountable modular buildings.

208

209 **Reuse Process**

210 The main pillars of circular economy (CE) consist of 11 "R" principles: Rethink, Refuse,
211 Reduce, Replace, Repurpose, Remanufacturing, Refurbish, Repair, Reuse, Recover, and
212 Recycle (Çimen 2021). Among these principles, material recycling and energy recovery are
213 given lower priorities in the CE framework, while extending the lifespan of products through
214 value retention processes (VRPs) like repurposing, remanufacturing, refurbishing, repairing,
215 and reusing is considered a higher level of circularity (Franco et al. 2021; Henry et al. 2020)
216 due to their higher value creation and preservation (Henry et al. 2020; Russell and Nasr 2023).
217 Despite these advantages, limited effort has been made to explore how VRPs specifically
218 enable the reuse of buildings.

219 The "R" principles of a circular economy align closely with waste management hierarchy
220 (Zhang et al. 2022), emphasizing the prioritization of reuse over recycling (Cole et al. 2019).
221 Deconstruction uploads the waste management hierarchy (Akinade et al., 2017) by recognizing
222 that product-level reuse is a more resource-efficient approach and offers better waste

223 prevention compared to recycling (Crowther 2001). Accordingly, the primary objective of
224 deconstruction is to preserve the original properties and structural integrity of building
225 components, ensuring their value is retained through reuse in various contexts (Diyamandoglu
226 and Fortuna 2015; Kibert 2003; Schultmann 2005; Chini and Bruening 2002).

227 The reuse of building components poses challenges due to uncertainties surrounding both the
228 future scenarios of the building itself (Hossain et al. 2020) and the future performance of
229 disassembled components (van den Berg et al. 2020). Several factors influence the potential
230 for reuse, even when disassembly is feasible (Iacovidou et al. 2021). For instance, the
231 reusability of building components may diminish if those components have experienced decay,
232 deformation, corrosion, or damage (Ottenhaus et al. 2023). The deterioration in quality of these
233 components represents the primary obstacle that hinders their reuse (Anastasiades et al. 2021;
234 Ottenhaus et al. 2023). While proper DfD design can address certain challenges related to ease
235 of disassembly and reusability, the effects of factors, such as the type, duration and direction
236 of loading and climate conditions (moisture content), on the mechanical properties of building
237 components are often underestimated (Ottenhaus et al. 2023). Notably, these effects can vary
238 significantly between different components, even within the same structural system (Ottenhaus
239 et al. 2023). In addition to these technical concerns, van den Berg et al. (2020) has highlighted
240 the critical role played by the availability of transportation, storage, and repair facilities in
241 facilitating the reuse of building elements. While the factors affecting building reuse are well
242 recognized, the actualization of building reuse remains largely unknown, as it is not commonly
243 practiced.

244 There has been a misunderstanding regarding the direct reuse of disassembled building
245 components in the next cycle even when they have incurred limited damage, as pinpointed by
246 Ottenhaus et al. (2023). This misunderstanding stems from a lack of comprehensive
247 understanding of the entire deconstruction process, from disassembly to reuse. Therefore, there

248 is an urgent need to gain new insights into the complete deconstruction process to bridge the
249 knowledge gap between disassembly (the first use cycle) and reuse (the subsequent life cycles).
250 Consequently, this study aims to understand the deconstruction process of modular building
251 systems. More specifically, the study aims to document the details of the deconstruction
252 process, including disassembly and reuse, and uncover the processes of how modular building
253 systems are disassembled at the end of their first use cycle and subsequently reused in the
254 second cycle.

255

256 **Methodology**

257 **Research Design**

258 The deductive research approach has long been used in construction management to test and
259 validate existing theories and resulting hypotheses through empirical research (Green et al.
260 2010). In contrast, when it comes to developing new concepts and theories, an inductive
261 approach is usually adopted (Green et al. 2010). This approach involves collecting, observing,
262 and analyzing data to critically question and expand upon traditional theoretical relationships
263 (Tan et al. 2021). Although the theoretical development of deconstruction is still in its early
264 stages, its principles and philosophies cannot solely rely purely on a inductive research process,
265 as they are influenced by the existing theoretical perspectives (Green et al. 2010), such as the
266 theory of building layers and waste management hierarchy (Crowther 2001). To advance the
267 theories related to deconstruction, this research adopts a combined deductive and inductive
268 approach. Such an integrated approach triggers a continuous interplay between existing
269 literature/theories and empirical data (Green et al. 2010), where the exploration and discovery
270 of new knowledge can benefit from theoretical underpinnings (Proudfoot 2023). Specifically,
271 the research begins by testing the established knowledge “deconstructing modular buildings

272 encompasses the processes of disassembly and reuse”. Subsequently, an inductive approach
273 was applied by critically questioning “what are the processes of disassembly and reuse?” This
274 question is formulated based on the argument that deconstruction intends to preserve the value
275 of the disassembled building elements primarily through reuse, as discussed in Literature
276 Review. The research approach adopted not only enables the verification and expansion of
277 traditional theories underpinning the deconstruction process but also enhances the
278 understanding of the new philosophies of deconstruction. **Fig. 1** shows the overall research
279 framework of the study.

280 <Please insert Fig. 1 here>

281 *Case Study*

282 In this research, a low-rise temporary, demountable, and relocatable social housing project was
283 selected and used to document its deconstruction process and identify the deconstruction
284 principles. This real-life case was chosen because it represents one of the first modular
285 buildings that has successfully executed the full processes of disassembly, relocation, re-
286 assembly, and reuse. Considering the limited availability of deconstruction practices, the
287 selected sole case study could provide unique and empirical insights into the current principles
288 and methodologies (Tan et al. 2024) adopted in the deconstruction process. It would contribute
289 to fostering the transfer of practice into new knowledge, thereby advancing the philosophies of
290 deconstruction. The single case study would offer insightful generalization to theoretical
291 propositions (Yin 2017; Mutikanga et al. 2023; Tan et al. 2024), although its generalizability
292 of findings to future cases (i.e., external validity) is challenged (Hallowell 2012). The
293 background of the case is briefly described below.

294 Nearly half of the Hong Kong population resides in public housing. As of the third quarter of
295 2023, the average wait time for public rental housing was 5.6 years (Housing Authority 2024).

296 Prior to moving into public rental flats, many vulnerable individuals and families have to live
297 for years in tiny, often subdivided, flats. Before the vulnerable can be moved into long-term
298 housing, the provision of short-term accommodation is one of the solutions to improve the
299 quality of life for those vulnerable groups. In the Chief Executive's Policy Address (2021), the
300 provision of transitional housing units was announced to address this pressing social need.
301 Transitional housing refers to the provision of short-term accommodation that facilitate the
302 transition of vulnerable groups into long-term housing (Legislative Council Secretariat 2019).
303 Using the modular construction method to build transitional housing is one of the short-term
304 accommodation options. These modular transitional housing projects are normally built on
305 vacant government-owned or privately-owned land. These projects are called "temporary"
306 because of a restriction to the length of land tenancy under the current transitional housing
307 scheme. The case study presented here is one of the transitional modular housing projects,
308 which was completed in 2020 and subsequently deconstructed in 2023 after a two-year
309 operation period due to the expiration of the land tenancy. Around 35 transitional modular
310 housing projects will probably be relocated in the future (Ling 2023).

311 The case was a four-story modular building, which consisted of a total of 68 modular units (**Fig.**
312 **2**). Each unit was constructed using structural steel frames and precast concrete slabs. All the
313 modular units were dismantled and reassembled in their original configuration at a different
314 location. The inter-module joints were designed using a dry connection mechanism (**Fig. 3**).
315 The disassembly of the modular units started in February 2023. All 68 modular units were
316 removed within three weeks and delivered to a temporary storage yard for inspection and
317 maintenance. All the modular units were reassembled in a new construction site in July 2023.

318 The modular building has adopted a number of Design of Disassembly, Reuse, and Relocation
319 principles (Crowther 2000). Firstly, modularity enables all interlinked components to be
320 assembled and disassembled (Roberts et al. 2023) in parallel. Secondly, the use of the same

321 type of accessible bolts and nuts inter-module connections not only allows the relative ease of
322 separation but also reduce the complexity of disconnection works (Crowther 2005). Thirdly,
323 steel, as a lightweight material, is used as the primary structural frame, making handling easier
324 and quicker (Crowther 2000). Moreover, a layering approach is adopted to prefabricate each
325 modular unit, allowing the separation of modular parts (Crowther 2000). Last but not the least,
326 material information is traceable in the study project, favoring the option of relocation
327 (Crowther 2000).

328 <Please insert Fig. 2 here>

329 <Please insert Fig. 3 here>

330

331 ***Data Collection***

332 This study employed three data collection techniques: (1) ethnographic site observation with
333 short-term passive participation, (2) semi-structured interviews, and (3) archival research.
334 These methods were applied in a single case study depicted above. The research design has
335 been approved by the Human Subjects Ethics Subcommittee of the authors' host university
336 (reference number: HSEARS20211015009).

337 Ethnographic research offers valuable insights into new construction practices by providing
338 fresh perspectives for practical improvement (Oswald and Dainty 2020). Traditional positivist
339 approaches dominant in the field of construction management (Pink et al. 2010) often struggle
340 to capture the intricate details of “how” practices unfold (Oswald and Dainty 2020). In this
341 context, the adoption of ethnographic research becomes particularly relevant, considering that
342 the selected case involves one of the pioneering instances of fully disassembling, relocating,
343 and reusing demountable modular buildings. By employing ethnographic research, practical
344 challenges on construction sites can be addressed, and new knowledge can be unearthed, as

345 demonstrated by van den Berg et al. (2020) who explored contractors' decision-making on
346 selective demolition. Participant observation serves as the primary method in ethnographic
347 research (Oswald and Dainty 2020). In this study, short-term and passive participation were
348 employed. Short-term observation involved collecting observational data over a period of six
349 months or less (Oswald and Dainty 2020). This approach was suitable in this research because
350 it took roughly six months to execute the entire process of disassembly and reassembly of all
351 modular units (i.e., from February to July 2023). Passive participation entailed observing the
352 site activities without actively engaging in site operations (Oswald and Dainty 2020). In this
353 study, the researchers were passive observers because they were not the registered site
354 personnel and were therefore not permitted to take part in any site activities in compliance with
355 local Construction Site (Safety) Regulations.

356 In this study, the research team conducted site visits at three distinct locations: Site A, where
357 the modular units were disassembled; Site B, where the modular units were stored, inspected,
358 and repaired; and Site C, where the modular units were reassembled. These site visits were
359 supplemented by the use of photography and video recording (Construction Industry Council
360 2023), referred to as "auto-ethnography" (Oswald and Dainty 2020). The interdisciplinary
361 research team comprised 13 experts and professionals, including a registered architect, a
362 registered structural engineer, four PhD holders (specializing in construction management,
363 construction economics, and structural engineering, respectively), two research assistants,
364 three photographers, and two industry advisors. During these site visits, the research team
365 documented the activities taking place on-site through written records, photographs, and videos.
366 Site A was visited three times. The research team observed the conditions of the modular
367 building prior to disassembly during the first visit. The second visit focused on the disassembly
368 of the first modular unit. The third visit centered on the disassembly of the final batch of
369 modular units. At Site A, the pre-deconstruction works and the disassembly process were

370 recorded. Site B were also visited three times. The initial visit involved observing the delivery
371 and storage of the first batch of modular units. The second visit focused on observing the
372 maintenance activities carried out at the storage yard. Visual observation was conducted to
373 assess any visible deformations, bulking, and corrosion of modular units. Additionally, the
374 general conditions of fire protection systems, interiors and exteriors of modular units were
375 recorded. During the final visit to Site B, the research team observed the transportation and
376 relocation of the modular units delivered from the storage yard. Site C was visited to observe
377 the reassembly process of the last batch of modular units. The cumulative participant
378 observation time during the disassembly, storage/maintenance, and reassembly phases of the
379 modular building was approximately 190 hours.

380 Ethnographic research through participant's site observation, however, is challenged by the
381 generalization, validity and reliability of its findings (Phelps and Horman 2010; Oswald and
382 Dainty 2020). It is therefore suggested that site observations should be conducted in
383 combination with other data collection methods, such as interviews, documentary data, and
384 focus groups, in order to complement and cross-validate each other (van den Berg et al. 2020).
385 A semi-structured interview approach was chosen for its ability to combine elements of both
386 the structured and unstructured interview styles, allowing the participant to express their
387 thoughts with some degree of flexibility (Guest et al. 2012). The participants selected for the
388 interview survey were individuals involved in the design, construction, deconstruction, and
389 reassembly phases of the case study. Such a purposive sampling approach was adopted to
390 control the level of variation among the interviewees and enable researchers to meet the goals
391 of the interview (Bazeley 2013) that aimed at exploring the construction, deconstruction, and
392 reassembly processes of modular units. It is worth noting that the contractor responsible for the
393 initial construction did not participate in the deconstruction and re-assembly processes. Instead,
394 the structural engineering consultant appointed by the client was involved in all phases.

395 Therefore, four representatives from the consultant, including the Director and three structural
396 engineers, were invited to participate in the interview survey as they were the key participants
397 in the case study. Previous studies involved a limited number of interviewees in their single
398 case studies (e.g., two safety managers in Martinez et al. 2020, and four experts in Al-Mhdawi
399 et al. 2022). Despite a limited sample size, the study adopted a mixed research method that
400 consisted of ethnographic research, archival research, and interview survey to cross-validate
401 the findings of each other. The primary interview questions focused on three main topics: (1)
402 validating the reusability of modular units assessed by the authors and (2) explaining the
403 processes of construction, deconstruction, and reassembly of modular units. The duration of
404 the interview was approximately 60 min.

405 Unpublished in-house documents were requested from interviewees, including a demolition
406 plan, a logistics plan, a condition survey report, a structural appraisal report, a mark-up plan,
407 and a reassembly plan, to obtain details of the disassembly and reuse processes. Specifically,
408 the demolition plan documented the demolition sequence of the modular building, the removal
409 sequence of module connections, design drawings of a layout plan and module connections, a
410 lifting plan, and safety precautions adopted during the disassembly process. This demolition
411 plan was reviewed to understand the sequence of disconnecting inter-module connections and
412 the sequence of removing modular units. The design drawings of module connections were
413 used to produce 3D diagrams in the study. The lifting plan showed the deployment of a crane
414 during the disassembly process by indicating the crane type, number of workers engaged, and
415 the designated working zone. The demolition plan and the lifting plan were used to develop a
416 schematic diagram about the disassembly process of modular units in this paper. The safety
417 plan presented safety measures implemented before and during the disassembly process,
418 including the erection of temporary hording and crane outrigger pads. Such information was
419 collected to understand the implementation of safety measures during the disassembly process.

420 The logistics plan documented the schedule of delivery of disassembled modular units from Site
421 A to Site B. It was obtained to estimate the approximate duration of the disassembly process
422 (i.e., three weeks). The condition survey report and structural appraisal report were collected
423 to understand the methodology and the process of quality inspection of modular units.
424 Correspondingly, the mark-up plan was obtained to indicate the specific replacement of fire
425 sealants and gementree boards required by each modular unit. The reassembly plan was gathered
426 to comprehend the reassembly sequence of modular units. These archived documents serve to
427 validate and substantiate the insights obtained through the interview process (Green et al., 2010)
428 and the site observations carried out by the authors.

429

430 *Data Analysis*

431 Prior to carrying out qualitative data analysis, various forms of data were documented,
432 including written records, interview scripts, archives, and the research team's reflections on the
433 photos and videos captured during the site visits. Specifically, the research team regularly held
434 internal meetings to discuss the implications of the visual materials and written diaries recorded
435 during site observations. For instance, a photo showing surface rust on a steel member of a
436 ground-floor modular unit suggested that ground moisture could be a contributing factor. All
437 of these records were treated as raw data, representing the unprocessed information collected
438 for further content analysis. A preliminary coding of raw data was conducted by assigning
439 semantic meaning to one or more sentences or graphs (Thompson 2022). For example, a
440 preliminary code assigned to the aforementioned photo was "ground-floor moisture leading to
441 surface rust". These preliminary codes were listed and used for either consolidation or
442 categorization in the following content analysis.

443 In order to validate the established knowledge, a deductive content analysis was performed to
444 answer the specific question: how is the deconstruction process, encompassing the disassembly
445 and reuse processes in existing literature, identified in the case study? To achieve this, a
446 predetermined coding scheme was developed based on existing theory, which was used to
447 categorize the raw data (Spearing et al. 2022). Specifically, the preliminary coding scheme
448 consisted of a set of codes, such as disassembly process and reuse process.

449 To address the second research question regarding the processes of disassembly and reuse, both
450 deductive and inductive content analytic techniques were used. This process involved
451 examining both existing knowledge and emerging insights from the case study (Spearing et al.
452 2022). Specifically, the second research question could be further refined as follows: “how well
453 do the existing disassembly process describe the case study experience?” and “what are the
454 newly identified reuse processes from the case study?” A deductive coding approach was
455 employed to address the first sub-question. By stemming from the existing literature, the
456 predefined coding scheme was designed for detailing the disassembly process, encompassing
457 codes such as disassembly sequence, disconnecting bolts and nuts joints, and dismantling
458 modules. Then an inductive coding approach was applied to address the second sub-question.
459 Specifically, the open coding approach was used to analyze the transcripts by extracting and
460 segmenting key ideas or concepts, categorizing them into (sub)themes, and summarizing the
461 contextual information (Spearing et al. 2022). As a result, additional themes, stemming from
462 the empirical observations, were incorporated into the coding scheme, namely, reverse logistic
463 process and value retention process, which served as sub-themes under the main theme of reuse
464 process. As the open coding process continued, further new themes were identified, including
465 take-back mechanism and traceability under the sub-theme of reverse logistics, and quality
466 inspection and touch-ups under the sub-theme of value retention. Intercoder reliability was

467 ensured through independent coding by two coders until consensus was reached on all the
468 codes (Spearing et al. 2022).

469 Following the theme development, an abductive reasoning approach was applied to theorize
470 data. Specifically, the study examined all possible theoretical explanations for the themes
471 (Thompson 2022; Charmaz 2006; Tavory and Timmermans 2014) by comparing the themes
472 with literature. For instance, the deconstruction theories of time-based building layering and
473 waste hierarchy and DfD principles were used to interpret the deconstruction process. Then the
474 study examined instances for which themes could not be interpreted by existing literature
475 (Thompson 2022; Tavory and Timmermans 2014). For example, the existing deconstruction
476 theories and DfD principles failed to explain to what extent the ease of disassembly would be.
477 The iterative engagement with theory and empirical data can trigger theoretical developments
478 by either refining, changing, adapting, or consolidating theory (Thompson 2022; Green et al.
479 2010).

480

481 **Results**

482 This section presents the findings of ethnographic research, semi-structured interview, archival
483 research of a case study. The results identify three primary processes and six sub-processes
484 associated with the deconstruction of a demountable modular building system. **Table 1**
485 summarizes the key findings originated from corresponding sources.

486

<Please insert Table 1 here>

487

488 *Disassembly Process*

489 Disconnecting Joints

490 The sequence of dismantling the modular building system consisted of the following major
491 steps, i.e., removing or disconnecting internal and external building service systems, removing
492 interior finishes located between adjacent modules, disconnecting joints, and dismantling
493 modules. This sequence is viewed as a sequential approach where one building part is removed
494 at a time (Santos and de Brito 2007; Sanchez and Haas 2018).

495 Firstly, the interior and exterior mechanical, electrical, and plumbing (MEP) equipment were
496 either removed or disconnected. Secondly, specific interior finishes, such as floor and wall
497 coverings and ceiling finishes, located between adjacent modules, were partially removed. This
498 step aimed to expose the inter-module connections, enabling workers to easily access them
499 during the disassembly process (O’Grady et al. 2021a). While the modular buildings were
500 designed to be reversible structures, certain components had connections that were irreversible
501 or inaccessible (van den Berg et al. 2020). For instance, the on-site tie-ins, such as power lines
502 and plumbing, were removed forcefully and thus, they were not reusable and disposed of.

503 After removing MEP equipment and interior finishes, the third step was to disconnect the
504 modular units by loosening the inter-module connections that held the adjacent four modules.
505 The accessibility issue was solved through an opening in the wall panel and thus the inter-
506 module connection could be accessed from the interior. Moreover, the design of the modular
507 units allowed the direct exposure and accessibility of the inter-module joints from the exterior
508 of the module. The inter-module connection comprised one T-section, two tie plates, two steel
509 tubes, and bolts and nuts. Initially, the T-section and upper and lower tie plates were loosened
510 by removing the bolts and nuts. Subsequently, the upper module was removed, and then the
511 steel tube connecting the upper and lower adjacent modules were dismantled. The
512 disconnection of inter-module connections (**Fig. 4**) can be viewed as a reverse process of their

513 initial connection, where the adjacent four modules were first connected by inserting the steel
514 tubes into steel hollow sections of each modular unit and subsequently securing them with the
515 T-section and tie plates by using bolts and nuts (**Fig. 5**).

516 <Please insert Fig. 4 here>

517 <Please insert Fig. 5 here>

518 According to the DfD principles, bolts and nuts connections could facilitate the easy separation
519 of modular components (Kitayama and Iuorio 2023). However, the findings of this study
520 revealed that disconnecting bolts and nuts joints was not as straightforward as anticipated. It is
521 worth noting that these connections were designed to provide structural rigidity, resulting in
522 tightly connected bolts and nuts (which implies structural integrity). It was also observed that
523 the steel tubes were tightly inserted, suggesting the presence of potential lock-in stress caused
524 by permanent load. In such cases, workers had to use a handy tool to tap the steel tube or the
525 hollow section, releasing the lock-in stress. The disconnection of bolts and nuts joints still
526 necessitates quality craftsmanship and hands-on skills of workers.

527

528 Disassembling Modular Units

529 The disassembly process of the modular units was carried out in a zone-by-zone manner.
530 Within each zone (**Fig. 6**), the modular units on the upper floors were removed first, followed
531 by those on the lower floors. It is viewed as a sequential disassembly because the disassembly
532 of the lower-floor modular unit requires the disassembly of the upper box concerning their
533 dependent geometric relationship. This sequence was also determined due to the congested site
534 conditions, where only one traffic pathway allowed the operation of a mobile crane. The zone-
535 by-zone assembly sequence had also been adopted during the initial construction, which was
536 necessitated by site constraints. Thus, the disassembly sequence can be seen as a reverse of the

537 assembly sequence. Since each modular unit consists of structure, skin, services, and fit-out
538 layers, removing a modular unit, also known as volumetric disassembly (Rausch et al. 2017),
539 can also be regarded as a parallel disassembly when multiple parts are removed at the same
540 time (Sanchez and Haas 2018; Deniz and Dogan 2014). Therefore, the disassembly sequence
541 of the modular building is a combination of sequential and parallel modes.

542 <Please insert Fig. 6 here>

543 As each modular unit was lifted, it was then placed on a 12-meter-long truck. A total of four
544 riggers and one crane operator were engaged to dismantle and position the modular unit to the
545 truck. The 68 modular units were removed within three weeks. Once all modular units were
546 transported to the storage yard, they were laid flat to undergo inspection and maintenance to
547 ensure their structural integrity. The disassembled modular units were placed in and delivered
548 from the storage yard following the rules of “first-in, last-out” (upper floor) and “last-in, first-
549 out” (lower floor). This arrangement facilitated the reassembly process when the modular units
550 were transported to the new project site, ensuring that they were assembled in the correct
551 sequence.

552 Concerning varying dead load spread on different modular units, it was restricted to reinstall
553 the modular units as their original configuration. As a result, the modular units were reused in
554 the same building system, probably limiting their interchangeability, flexibility and
555 adaptability. It is worth noting that the reassembly sequence adopted a floor-by-floor manner.
556 The modular units on the lower floors were reassembled, followed by those on the upper floors.
557 This approach was used because there was ample space available, allowing the mobile crane
558 to move around. Generally, the floor-by-floor assembly/disassembly sequence may offer better
559 structural stability compared to the zone-by-zone approach. This is because in the floor-by-
560 floor sequence, the load is transferred linearly and distributed evenly, whereas the zone-by-

561 zone sequence may induce angled load paths through the entire structure. For instance, when
562 removing the modules in zone 3 adjacent those in zone 4, safety measures were implemented
563 to ensure that the modular units in zone 4 would not topple or collapse by enclosing the lifting
564 zone and installing temporary support. This is because the pyramid-like structure of zone 4
565 might have a higher center of gravity, making it more vulnerable to instability and tipping over
566 if it is not adequately supported. The present findings suggest that the sequence of removing
567 modular “boxes” should be determined in a safe manner that ensures the structural integrity of
568 the remaining parts throughout the disassembly process.

569

570 ***Reverse Logistics***

571 Take-back Mechanism

572 It was found that the public client appointed a design-build contractor to handle the disassembly,
573 transportation, refurbishment, and re-assembly of the original modular building on a new site.
574 It is important to note that this contractor was not engaged in the design, manufacture and
575 assembly of the original modular building. The disassembly and reassembly works were not
576 initially considered in the prior design-build procurement. At the end of service life of the
577 modular building, the client initiated an open tendering process to procure a suitable contractor
578 who could handle both the deconstruction (i.e., disassembly, maintenance, and reassembly) of
579 the original building and the design and construction of new modular buildings. A new
580 contractor was thus selected through open-tendering to ensure transparency, accountability,
581 and public interest, avoiding potential biased negotiations with the original contractor engaged
582 in public projects. This procurement method proved that the used building products were not
583 necessarily returned to the original contractor. Instead, they were taken back by a new
584 contractor who was responsible for the entire deconstruction process, including disassembly,
585 maintenance/repair, and reassembly, regardless of whether they were involved in the initial

586 assembly or not. Essentially, the ownership of the modular building remains with the same
587 public client throughout both the initial and subsequent use cycles. Therefore, the client could
588 be able to provide the deconstruction contractor with necessary specifications of the original
589 modular design and material information as the deconstruction contractor needs to understand
590 the connection design and replaceable materials.

591

592 Traceability

593 To ensure the accurate reassembly of each modular unit in its original configuration, a unique
594 quick response (QR) code was assigned to each modular unit enabling tracking and locating
595 throughout disassembly, transport, and re-assembly. The QR code contains essential
596 information about each modular unit, including dimension, floor location, dates and times of
597 disassembly, delivery, and reassembly, as well as details of the crane and truck used. On-site
598 engineers could easily access module information by scanning the QR codes, which greatly
599 assisted in tracking the entire deconstruction process, identifying the location of each modular
600 unit, and improving the efficiency of the reassembly process. However, a few limitations of
601 the QR code system deployed were observed. The use of two A4 papers to display QR codes
602 on the front surface and inner side of each modular unit has proven problematic, as these papers
603 are easily damaged or lost. One potential solution could be to engrave the QR codes directly
604 onto the interior and exterior surfaces of the modular units. However, this approach may
605 influence the finishes and overall appearance of the decorations. Moreover, the QR codes could
606 become blurred due to occupants' interactions, as noted by a site engineer. Furthermore, there
607 might be potential security risks associated with the existing QR codes, as unauthorized
608 individuals could be able to scan and access them and modify the information. The third
609 limitation of the current QR code system lies in its limited scope of providing basic information

610 about the modular units and the deconstruction processes, while detailed information about
611 inspection and refurbishment of the modular units was not recorded.

612

613 *Value Retention*

614 Quality Inspection

615 A three-stage inspection process was implemented to assure the quality of the reused modular
616 units. Specifically, the first stage involved conducting a condition survey of the modular units
617 prior to disassembly. Based on the archival information obtained from interviewees, no
618 structural abnormalities such as cracking or deformation were observed, indicating that the
619 interior and exterior of the modular units were in good condition. During the second stage, a
620 condition survey was conducted immediately after the modular units were disassembled. The
621 exterior and interior sides of each module were extensively photographed, resulting in more
622 than 500 photos that were submitted for inspection, comments, and approval by relevant
623 statutory authorities. The inspection survey revealed that the conditions of the modular units
624 before and after disassembly remained largely unchanged, indicating no visible damage or
625 deflection during the disassembly process. As a result, it was determined that structural
626 members were in good condition and were reusable. The condition surveys conducted both
627 before and after disassembly relied primarily on visual observation, which could be time-
628 consuming and subjective as it heavily relies on the judgement of inspectors (Xu and Yang
629 2020; Yeum and Dyke 2015).

630

631 The first two quality inspection procedures were employed to determine the suitability of the
632 modular units for direct reuse, the need for repairs or refurbishment, or the complete rejection
633 of reuse, whereas the third stage aimed to assure the quality of modular units before reuse. In
634 the third stage of inspection, a detailed structural appraisal was conducted after the touch-ups

635 and before the reassembly of the modular units. The sampling size of 10%, which equated to 7
636 modules out of a total of 68, were chosen for structural appraisal, although scientific evidence
637 supporting the chosen sampling approach is limited. The structural appraisal encompassed a
638 series of non-destructive tests, including dimensional measurement, coating thickness
639 measurement, and weld test. Dimensional measurements in length, height, and width of the
640 exposed steel members were carried out. The test results were compared to the approved design
641 to determine whether there exist significant differences in sectional dimensions and thickness
642 (i.e., >1mm). As a result, it was concluded that the tested members were examined without
643 significant deformation. The thickness of the galvanized coating and fire protection painting
644 on the exposed steel members was also measured. The measured coating thickness of the
645 surveyed steel members either matched or exceeded the approved thickness, indicating
646 enhanced fire resistance and anti-corrosion protection. Furthermore, magnetic particle test was
647 performed to detect surface or near-surface flaws in welded column to beam joints. The results
648 indicated that no defects were found in the welded joints, affirming the reusability of the
649 column to beam joints in the modular units.

650

651 Touch-ups

652 Touch-ups plays a crucial role in ensuring the reusability of modular components, enabling
653 their continued use in subsequent service life cycles. Upon the two years of use, module joints
654 and exposed steel structural members were found in good condition, exhibiting no significant
655 deformation, bending, or damage. However, slight surface rusts were observed in a few steel
656 components. For instance, slight surface rusting was observed on the back of a T-section over
657 the inter-module connections. The rust stain could be attributed to water accumulation in the
658 gaps between the T-section and the steel columns, potentially leading to surface corrosion.
659 Localized surface rusting was observed near the beam-column joints of a specific module (label

660 2-3-1, **Fig. 6**). This was likely caused by prolonged water presence in the gaps between adjacent
661 modules. Additionally, surface rust stains were found on a steel column of a top-floor unit
662 (label 3-1-5, **Fig. 6**), possibly resulting from rainwater ingress. Furthermore, surface rusting
663 was detected on a steel beam of a ground-floor module (label G-2-5, **Fig. 6**), likely due to
664 exposure to ground moisture. Minor surface rust stains were detected on a top cover panel of a
665 specific second-floor unit labelled as 2-1-1 shown in **Fig. 6**. The rust stain likely resulted from
666 rain ingress through the gap between the second and third floor modules. In three modular units,
667 the fireproof painting had peeled off from the steel members, potentially resulting from
668 scratches during assembly or disassembly. To address these issues, touch-ups were performed
669 by removing rust stains and repainting the affected connections and steel members. Protective
670 zinc coating and fireproofing coating were applied to ensure enhanced protection against
671 corrosion and fire hazards. Fire sealants and gementree boards were also replaced to ensure the
672 continued effectiveness of the fire protection system for subsequent use. A small number of
673 wall and floor tiles in a toilet showed signs of cracking and peeling due to normal wear and
674 tear. These tiles were subsequently removed and replaced.

675

676 **Discussion**

677 This section discusses the key lessons derived from the aforementioned deconstruction process
678 of a modular building system by uncovering that (1) DfD does not inherently ensure effortless
679 ease of disassembly and (2) factors such as client ownership, digital material tracking, and ease
680 of value retention play crucial roles in facilitating building reuse.

681

682 *Ease of Disassembly*

683 It has been widely recognized that modular design, lightweight materials, and dry connections
684 enable ease of disassembly of building components. While the current empirical findings
685 support the use of these DfD principles, it is important to note that modularity and dry
686 connections do not guarantee effortless ease of disassembly. The empirical findings offer new
687 insights into the effectiveness and practicality of DfD principles.

688

689 Bolts and Nuts Joints

690 The utilization of bolts and nuts joints to enable damage-free dismantling of building
691 components is widely acknowledged. However, limited studies have empirically substantiated
692 the ease of disassembly achieved through the use of bolts and nuts joints in real deconstruction
693 projects. A common misconception arises when it is assumed that bolts and nuts joints
694 automatically guarantee effortless easy disassembly. In the current case, the bolts and nuts
695 connections were designed to facilitate the detachment of modular units without causing
696 structural damage. However, the on-site observations revealed that the disconnection of inter-
697 module joints using bolts and nuts did not guarantee effortless results due to potential lock-in
698 stress. Thus, workers had to manually release the lock-in stress, highlighting the demanding
699 nature of manual handling during the systematic disassembly process (Akinade et al. 2017;
700 Allam and Nik-Bakht 2023; van den Berg et al. 2020). Surprisingly, there is a lack of research
701 addressing the issue of lock-in stress associated with bolts and nuts connections. This indicates
702 the necessity for further advancements in DfD connections that not only prioritize structural
703 integrity but also facilitate easier disconnection by minimizing the reliance on manual handling
704 during the disassembly process.

705 Furthermore, it is crucial to consider that the modular building examined in this research had a
706 relatively short operational period of just two years. If the building's operational lifespan is
707 extended, there could be additional uncertainties arising from dead loading effects, increased
708 lock-in stress, and the degradation of building conditions resulting from occupants' use over
709 time. Therefore, it is vital to recognize that factors such as the duration of use, type and
710 direction of loading, and prevailing climate conditions can potentially impact the ease of
711 disassembly and reassembly (Ottenhaus et al. 2023). Future studies are recommended to
712 explore different types of DfD joints and assess the influence of loading and climate conditions
713 on both the ease of disassembly and reuse. The adoption of innovative technologies, such as
714 automated (dis)connecting device (Picard et al. 2024), may enhance the precise of
715 (dis)assembly and thus reduce the reliance on manual handling. Additionally, it is advised to
716 validate the present findings when alternative module connection systems are used.

717

718 Disassembly Sequence

719 Previous research has examined either sequential (Sanchez and Haas 2018) or parallel (Sanchez
720 et al. 2019) approaches to disassembling building parts. In the current case study, a hybrid
721 approach combining sequential and parallel disassembly methods was observed. The removal
722 process followed a sequential order for internal and external building service systems, interior
723 finishes located between adjacent modules, bolts and nuts connections, and modular units. This
724 sequential approach was necessary as the modules could not be disassembled if the
725 interconnected components (such as power lines and flooring between adjoining modules) were
726 not disconnected.

727 Regarding the disassembly of modular units, a sequential approach was adopted, where one
728 unit was removed at a time. However, it is important to note that the modular design allowed

729 certain building layers (such as structure, skin, services, space, and stuff) to be constructed as
730 a single unit and removed together. This approach can be seen as a form of parallel disassembly,
731 as it minimizes the separation of different layers and reduces the risk of damage. The findings
732 emphasize the importance of incorporating modularity into DfD principles. The modular
733 design enables the parallel disassembly of individual modular units, potentially reducing
734 disassembly time and cost (Smith and Hung 2015) compared to a sequential method.

735 Given that the modular building was only operated for two years, it was still technically
736 reusable until it would reach its end of life. When the modular building system reaches the end
737 of its life, it becomes essential to investigate the disassembly process of each modular unit as
738 its disassembly method may be different with that for demounting modular boxes. Van den
739 Berg (2020) documented a sequential disassembly routine for disassembling a temporary
740 modular building that ends of its service life. While non-destructive disassembly was employed
741 to recover the modular façade, destructive disassembly had to be used deconstruct ceiling tiles
742 and floor slabs (van den Berg et al. 2020). Similarly, it is anticipated that destructive
743 disassembly would likely be necessary for the current individual modular units because
744 dismantling welded steel beams and columns in each unit could cause structural damage and
745 increase the complexity of the disassembly process. Future research is recommended to explore
746 systematic disassembly approaches for individual modular units that have reached the end of
747 their lives. This should consider the interdependence of components, as well as the residual
748 environmental and economic value, to determine which parts should be recovered and which
749 should be disposed of (Sanchez and Haas 2018).

750

751 *Linkage between disassembly and reuse*

752 A misunderstanding arises from the assumption that demountable components are inherently
753 reusable, as indicated by Ottenhaus et al. (2023). To clear up this misconception, the present
754 empirical findings suggest that client ownership, digital material tracking, and ease of value
755 retention are essential for bridging the gaps in procurement, information, and quality between
756 disassembly and reuse.

757

758 Client Ownership

759 The study uncovered that the disassembly and repair of modular units were carried out by a
760 new contractor who was not involved in the initial construction phase. However, the ownership
761 of the modular building remained with the same public client throughout both the initial and
762 subsequent use cycles. This finding has significant implications. Firstly, the successful
763 implementation of the innovative take-back mechanism relies on the continuity of ownership
764 for the modular building. With unchanged ownership, the client can reuse the modular units in
765 future projects since finding a new client willing to use secondary building products can be
766 uncertain. This continuity of ownership helps address concerns about potential economic losses
767 (Anastasiades et al. 2021) due to limited market demand for secondary building parts. By
768 retaining ownership, the client assumes responsibility for promoting the reuse of the modular
769 building in subsequent use cycles. Building on past practical experience, it has been
770 demonstrated that minimizing changes in client ownership is an effective approach to ensuring
771 the feasibility of material reuse (Big Buyers Initiative 2020). This is particularly relevant for
772 city building agencies that aim to utilize building materials in their own renovation and
773 construction projects (Big Buyers Initiative 2020).

774 Secondly, the retention of client ownership sets it apart from conventional take-back
775 mechanisms like Extended Producer Responsibility (EPR). ERP emphasizes that suppliers bear
776 responsibility for their services throughout the entire lifecycle of the building (Charef et al.
777 2022). Under EPR, it is envisioned that when a product reaches the end of its lifecycle, the
778 client returns salvaged building components to the contractor, supplier, or manufacturer who
779 then take on the responsibility of promoting disassembly and reuse instead of disposal. While
780 this product as service model has been implemented in a few public projects (e.g., Brummen
781 Town Hall in the Netherlands, Jones et al. 2017), the demand for the reuse of secondary
782 building parts remains uncertain. Building components differ from typical consumer products,
783 as potential new clients may exhibit hesitancy in purchasing secondary building parts due to
784 concerns regarding quality, remaining lifespan, hidden risks, and liability. Given these hurdles
785 of implementing producer responsibility, the present study implies the feasibility of client
786 ownership in promoting building reuse.

787 There are potential risks of significant damage occurring during the stages of use, lifting, and
788 transport. It is crucial for the client and the new contractor to establish an emergency plan to
789 sourcing replaceable modular units in such cases. While approaching the original contractor
790 for replacements is a possibility, conflicts may arise due to intellectual property rights
791 associated with the design of modular joints, leading to complex contractual relationships
792 between the client and the contractors involved. On the other hand, producing new
793 replacements by a new contractor may be an alternative, but the economic viability of
794 manufacturing a few modular units relative to creating a new mould can pose challenges for
795 both the client and the contractor. Concerning the potential risks of unexpected damage to
796 modular units, it appears that EPR may be a more viable option, as the original contractor can
797 be responsible for repairing and replacing damaged components with predetermined charges.
798 However, the consideration of EPR should occur during the early procurement phase of the

799 primary construction. The uncertain financial and contractual risks associated with
800 implementing EPR for a whole building have not been explored yet.

801 In the present case study, the client re-tendered the deconstruction works as the original Design-
802 Build procurement did not take deconstruction into account. It is recommended that a whole-
803 life-cycle approach, such as the Design-Build-Deconstruction procurement (Yang et al. 2022),
804 be considered for future projects involving demountable and reusable buildings, although this
805 new approach has not yet been tested. In such cases, scenarios for the second use cycle should
806 be planned early, considering the uncertainties that significantly challenge the client.

807 There is ongoing debate regarding ownership and take-back mechanism for building reuse,
808 particularly as project delivery methods have not been established for deconstruction projects
809 (Allam and Nik-Bakht 2023). Future studies are needed to systematically identify the financial
810 and contractual risks associated with different ownership models and take-back mechanisms in
811 building reuse.

812

813 Digital Material Tracking

814 One of the key principles that enables building relocation and reuse is maintaining
815 comprehensive information about the building's manufacturing, assembly, disassembly
816 processes, material and component life expectancy, and maintenance requirements (Crowther
817 2000). The case study adopted a digital solution to track modular units, which provide
818 traceability for reusable building parts by collecting and sharing data (Giovanardi et al. 2023)
819 across multiple use cycles. It further enhances transparency of the overall deconstruction
820 processes (Zhai et al. 2019) and establishes trust and collaboration among different
821 stakeholders involved in the project (Ellsworth-Krebs et al. 2022).

822 To address the limitations of the existing QR code system in terms of limited data information
823 and potential security issues, future research directions are offered to achieve traceability and
824 transparency of building information throughout the entire deconstruction process. Firstly, to
825 address this issue and improve information security and data protection, the implementation of
826 disruptive technologies like blockchain has been suggested (Yu et al. 2022; Li et al. 2022).
827 Blockchain technology can enhance security, especially when more detailed data such as
828 supplier information, reusability records, and inspection reports are recommended to be
829 included. Secondly, the QR code system can be further expanded with various scales, including
830 (i) material-scale information, e.g., origin, supplier, specification, and certificate, (ii)
831 component-scale information, e.g., connection design, designed service of life, reusability,
832 inspection records, and refurbishment records, (iii) modular unit-scale data, e.g., configuration,
833 weight, size, and embodied carbon, and (iv) process-scale data, e.g., dates and time of
834 disassembly, delivery, refurbishment and re-assembly, and disassembly sequence. Given the
835 potential for multiple reuse cycles and the involvement of various contractors in
836 (de)construction of modular units, it becomes crucial to collect, store, share, analyze, and
837 manage life cycle data on modular units over time. Contractors who were not involved in the
838 initial design and construction stages can access the QR code system to understand the material
839 lifespan and disassembly sequence. Furthermore, they could follow the designated
840 maintenance instructions to procure appropriate replacement materials and carry out necessary
841 maintenance.

842

843 Ease of Value Retention

844 VRPs have generally been overlooked during building deconstruction. This research represents
845 a pioneering study that emphasizes the importance of value retention during the building
846 deconstruction process. Some studies have incorporated VRPs in their life cycle assessments

847 of building component reuse, suggesting that demountable building components may not be
848 suitable for direct reuse in the next cycle without prior VRPs (van Stijn et al. 2021; Yang et al.
849 2024). These processes, along with quality inspection, are essential for ensuring that modular
850 units can be reused in the second use cycle. In the present study, the deteriorated lifespans of
851 building components typically resulted from material degradation, manual handling, and
852 improper occupant behaviors. The lifespans of building components can further influence the
853 type and intensity of VRPs, such as repair, replacement, and refurbishment (van Stijn et al.,
854 2021).

855 By differentiating between “product core” (Krystofik et al. 2018; Goodall et al. 2014) and non-
856 core components of a modular building system (Yang et al. 2024), it is recognized that certain
857 non-core components with shorter life expectancies require more extensive replacement due to
858 faster degradation from wear and tear (IRP 2018) compared to product cores with longer life
859 expectancies. For example, the steel frame, as the core structure of the modular system, was
860 reused after minor repairs, such as applying protective zinc and fireproofing coating. Non-core
861 components like fire sealants, gementree boards, and a few wall and floor tiles were replaced due
862 to their shorter lifespans. In the long term, non-core components such as bolts and nuts joints
863 may require extensive replacement when the frequent loosening and fastening of connections
864 during the disassembly and reassembly processes result in decreased joint strength. Interior
865 refurbishment may also be intensive due to the longer use period and possible improper
866 occupant behaviors.

867 The successful implementation of various VRPs for core and non-core components relies on
868 their independent geometric relationship. The separation of non-core components from the core
869 structure allows for the replacement of non-core components without affecting the core
870 structure. Instead of discarding the entire modular unit, the separation of the damaged non-core
871 part from the core structure enables the implementation of VRPs targeting the damaged part

872 without compromising the lifespan of the core structure. Consequently, the entire modular unit
873 could be continuously used. This finding implies that the adoption of building layering design
874 not only allows for the separation of building layers (Crowther 2001) but also facilitates the
875 ease of repair and replacement of less durable non-core components (Crowther 2000).

876

877 **Theoretical and Practical Implications**

878 This paper contributes to the existing body of knowledge on deconstruction by offering
879 empirical insights into the deconstruction process of a low-rise modular building. Theoretically,
880 this study is pioneering in its investigation of the disassembly and reuse processes in a modular
881 building project, which bridges the knowledge gaps that exist between these two processes.
882 Additionally, this paper validates certain DfD principles that either fully or partially enable
883 ease of disassembly and reuse. In terms of practical implications, managerial approaches such
884 as procurement innovation and technology innovation play an important role in building reuse.
885 The lessons learned from deconstructing demountable modular buildings can help construction
886 professionals better respond to similar deconstruction projects in the future.

887 Specifically, the studied modular building system is demountable due to the adoption of several
888 DfD principles, including modular construction, bolts and nuts connections, lightweight
889 materials, and building layering approach. While these principles enable the disassembly of the
890 modular building system, the ease of disassembly is not inherently guaranteed due to potential
891 lock-in stress of bolts and nuts joints. This finding has three implications. Firstly, it provides
892 valuable information for industry practitioners to improve planning and management of manual
893 handling, equipment, tools, and craftsmanship to release the lock-stress of the connections
894 during the disassembly process. Secondly, it highlights a misunderstanding in existing DfD
895 principles, where the use of bolts and nuts joints is mistakenly assumed to automatically

896 guarantee ease of disassembly without considering potential lock-in stress of the connections.
897 Previous studies have failed to fully comprehend the practicality of DfD principles due to a
898 lack of empirical research or insufficient integration of feasible DfD principles into practice.
899 Lastly, the finding suggests the need for an in-depth investigation of various DfD connections
900 and assessment of their potential lock-in stress, which may hinder ease of disassembly.

901 Another misconception that is clarified is the assumption that demountable components are
902 automatically reusable. By uncovering the disassembly and reuse processes, this paper fills a
903 gap in the procurement of building reuse. The introduction of a novel take-back mechanism
904 with client ownership offers fresh insight into how building reuse can be procured in public
905 projects. This new circular business model, characterized by client ownership and the return of
906 products to a new contractor, exemplifies the application of circular economy principles in
907 practice, as the owner and contractor adapt their business models to this new paradigm.
908 Moreover, a technology-driven material tracking system that provides important information
909 repository is essential for effective deconstruction planning, management, and execution. By
910 bridging the information gap between disassembly and reuse, this digital tracking system can
911 be improved and implemented in future deconstruction projects to facilitate the exchange of
912 information between successive use cycles. Furthermore, the quality gap between successive
913 use cycles is a major concern in building reuse. VRPs play a crucial role in repairing and
914 replacing obsolete components and refurbishing the building to a new state. The adopted
915 building layering approach facilitates the ease of value retention by separating obsolete
916 components from the modular frame and replacing them with new ones. To conclude, the
917 findings of this paper bridge the procurement, information, and quality gaps between
918 disassembly and reuse, making a theoretical contribution to the existing knowledge on
919 deconstruction. These valuable lessons can guide construction professionals in better planning
920 and managing similar deconstruction projects in the future.

921

922 **Concluding Remarks**

923 There has been an increasing trend in the provision of low-rise temporary, demountable, and
924 relocatable modular building systems in light of the pressing need for emergency facilities
925 worldwide due to their fast on-site delivery. These buildings often fulfill their intended purpose
926 before reaching the end of their designed service lives. Disassembling and reusing these
927 facilities can help preserve their value in the economy and align with the principles of
928 sustainability and the circular economy. This empirical study presents a pioneering and detailed
929 examination of the deconstruction process of a low-rise demountable modular building system,
930 showcasing its successful disassembly, relocation, and reuse in real-life scenarios.

931 Regarding the deconstruction process, the empirical findings indicate that the disassembly
932 process involves a hybrid sequential and parallel disassembly of modular units, while the reuse
933 process consists of four sub-processes: take-back, material tracking, quality inspection, and
934 touch-ups. Based on these findings, the study contributes to the existing knowledge on
935 deconstruction by revealing that (1) DfD does not inherently ensure effortless ease of
936 disassembly and (2) factors such as client ownership, digital material tracking, and ease of
937 value retention play crucial roles in facilitating building reuse. These new empirical findings
938 provide a deeper understanding of the deconstruction process by bridging the procurement,
939 information, and quality gaps between disassembly (the first use cycle) and reuse (the second
940 use cycle).

941 Moreover, this research has significant practical implications. The exploration of factors such
942 as ease of disassembly, take-back mechanisms, technology-driven traceability, and ease of
943 value retention offers a systematic approach for practitioners involved in deconstruction
944 projects. The identified processes and factors that link disassembly and reuse should be

945 carefully considered to enable multiple reuse cycles, ultimately supporting the transition
946 towards circular reuse of modular buildings.

947 However, it is important to acknowledge some limitations that may hinder the broader
948 application of deconstruction. The implications of this study may not directly apply to projects
949 that have not incorporated DfD principles, as they may involve different disassembly and reuse
950 processes. The results may also be specific to low-rise temporary and demountable buildings,
951 which represent a particular type of construction typology. Furthermore, due to the limitations
952 of a single case study in terms of external validity, further empirical studies are needed to
953 validate the present findings by comparing similar or different construction typologies (e.g.,
954 high-rise demountable modular buildings) and enrich the existing knowledge on building
955 deconstruction. Additionally, a comprehensive understanding of the deconstruction process,
956 which enables both reuse and recycling, should be investigated, considering that not all
957 building parts are reusable.

958 Based on the above findings, future research can focus on two primary domains. Firstly,
959 structural engineering research should be conducted to develop easily demountable and
960 interchangeable modular systems and understand the influences of various loading conditions,
961 duration, climate factors, and the frequency of assembly and disassembly on disassembly
962 performance and reusability. Secondly, engineering management research is needed to address
963 key issues that can bridge the gaps between disassembly and reuse. This includes exploring
964 contractual and financial risks in procuring deconstruction projects, technological
965 advancements in material tracking, and the development of disassembly methodologies for
966 obsolete modular units.

967

968 **Data availability statement**

969 Some data (i.e., interview scripts and records, photos, and videos of site observations) that
970 support the findings of this study are available from the corresponding author upon reasonable
971 request. Some data (i.e., a demolition plan, a logistics plan, a condition survey report, a
972 structural appraisal report, a mark-up plan, and a reassembly plan) used during the study are
973 proprietary or confidential in nature and may only be provided with restrictions. Restrictions
974 are applied to the availability of these archival research data if the participants of the study give
975 written consent for their data to be shared publicly.

976

977 **Acknowledgements**

978 This paper forms part of the research projects funded by the Construction Industry Council of
979 Hong Kong S.A.R., and the General Research Fund (No. 15221722), the Research Grant
980 Council of Hong Kong S.A.R., from which other deliverables will be produced with different
981 objectives/scopes/methodology but sharing common background and findings of the case study.
982 The Housing Bureau of Hong Kong S.A.R., Wilson & Associates Ltd., Woon Lee Construction
983 Co., Ltd., CNQC International Holdings Limited., CNQC Intelligent Construction (Hong Kong)
984 Limited, who contributed their time and knowledge are greatly acknowledged. We also thank
985 editors and anonymous reviewers for their constructive comments.

986 **References:**

987 Akinade, O. O., L. O. Oyedele, M. Bilal, S. O. Ajayi, H. A. Owolabi, H. A. Alaka, and S. A.
988 Bello. 2015. "Waste minimisation through deconstruction: A BIM based Deconstructability
989 Assessment Score (BIM-DAS)." *Resour. Conserv. Recycl.* 105, 167-176.

990 Akinade, O. O., L. O. Oyedele, S. O. Ajayi, M. Bilal, H. A. Alaka, H. A. Owolabi, S. A. Bello,
991 B. J. Jaiyeoba, and K. O. Kadiri. 2017. "Design for deconstruction (DfD): Critical success
992 factors for diverting end-of-life waste from landfills." *Waste Manage.* 60, 3-13.

993 Al-Mhdawi, M. K. S., M. P. Brito, M. Abdul Nabi, I. H. El-Adaway, and B. S. Onggo. 2022.
994 “Capturing the impact of COVID-19 on construction projects in developing countries: A case
995 study of Iraq.” *J. Mange. Eng.* 38(1), 05021015.

996 Allam, A. S., and M. Nik-Bakht. 2023. “From demolition to deconstruction of the built
997 environment: A synthesis of the literature.” *J. Build. Eng.* 64, 105679.

998 Anastasiades, K., J. Goffin, M. Rinke, M. Buyle, A. Audenaert, and J. Blom. 2021.
999 “Standardisation: An essential enabler for the circular reuse of construction components? A
1000 trajectory for a cleaner European construction industry.” *J. Clean. Prod.* 298, 126864.

1001 Basta, A., M. H. Serror, and M. Marzouk. 2020. “A BIM-based framework for quantitative
1002 assessment of steel structure deconstructability.” *Auto. Constr.* 111, 103064.

1003 Bazeley, P. 2013. *Qualitative data analysis: Practical strategies*. Los Angeles, CA: Sage.

1004 Bertino, G., J. Kissler, J. Zeilinger, G. Langergraber, T. Fischer, and D. Österreicher. 2021.
1005 “Fundamentals of building deconstruction as a circular economy strategy for the reuse of
1006 construction materials.” *Appl. Sci.* 11(3), 939.

1007 Big Buyers Initiative. 2020. *Public procurement of circular construction materials: key
1008 takeaways from the Big Buyers Initiative working group*. ICLEI – Local Governments for
1009 Sustainability, European Secretariat.

1010 Brand, S. 1994. *How buildings learn*. Viking, New York.

1011 Charef, R., W. Lu, and D. Hall. 2022. “The transition to the circular economy of the
1012 construction industry: Insights into sustainable approaches to improve the understanding.” *J.
1013 Clean. Prod.* 364, 132421.

1014 Charmaz, K. 2006. *Constructing grounded theory: A practical guide through qualitative
1015 analysis*. London: SAGE.

1016 Chen, L.K., R.P. Yuan, X.J. Ji, X.Y. Lu, J. Xiao, J.B. Tao, X. Kang, X. Li, Z.H. He, S. Quan,
1017 and L.Z. Jiang. 2021. "Modular composite building in urgent emergency engineering projects:
1018 A case study of accelerated design and construction of Wuhan Thunder God Mountain hospital
1019 to COVID-19 pandemic." *Auto. Constr.* 124, 103555.

1020 Chief Executive's Policy Address. 2021. *Policy Address*. Available at:
1021 <https://www.policyaddress.gov.hk/2021/eng/policy.html>. Accessed on 13 Oct. 2021.

1022 Chini, A. R., and S. Bruening. 2002. "Design for deconstruction and materials reuse CIB task
1023 group 39 - deconstruction meeting CIB." In *International Council for Research and Innovation*
1024 *in Building Construction Task Group 39: Deconstruction*. Karlsruhe, Germany.

1025 Construction Industry Council. 2020. MiC projects. <https://mic.cic.hk/en/MicProjects>
1026 (accessed on 7 Oct. 2021).

1027 Construction Industry Council. 2023. *Technical Report on the Deconstruction, Relocation and*
1028 *Reinstallation of MiC modules in Nam Cheong 220 Transitional Housing Project*. Authors:
1029 Luk, C., Y. Yang, K. F. Chung, *et al.* 31 Oct. 2023. <https://mic.cic.hk/en/Publications>
1030 (accessed on 15 Jun. 2024).

1031 Çimen, Ö. 2021. "Construction and built environment in circular economy: A comprehensive
1032 literature review." *J. Clean. Prod.* 305, 127180.

1033 Cole, C., A. Gnanapragasam, T. Cooper, and J. Singh. 2019. "An assessment of achievements
1034 of the WEEE Directive in promoting movement up the waste hierarchy: experiences in the UK."
1035 *Waste Manage.* 87, 417-427.

1036 Crowther, P. 2000. "Developing guidelines for designing for deconstruction." In
1037 *Deconstruction-Closing the Loop Conference Proceedings*. Building Research Council.

1038 Crowther, P. 2001. "Developing an inclusive model for design for deconstruction." In *Proc.,*
1039 *the CIB Task Group 39-Deconstruction Meeting*, 1-26. Wellington, New Zealand.

1040 Crowther, P. 2005. "Design for disassembly—themes and principles". *Environ Design Guide.*
1041 v. 2, p. 1–7.

1042 Denhart, H. 2010. "Deconstructing disaster: Economic and environmental impacts of
1043 deconstruction in post-Katrina New Orleans." *Resour. Conserv. Recycl.* 54(3), 194-204.

1044 Deniz, O. S., and E. Dogan. 2014. "Building façade system for deconstruction." *J. Sustain.*
1045 *Archit. Civil Eng.* 8(3), 59-74.

1046 Diyamandoglu, V., and L. M. Fortuna. 2015. "Deconstruction of wood-framed houses:
1047 Material recovery and environmental impact." *Resour. Conserv. Recycl.* 100, 21-30.

1048 Ellsworth-Krebs, K., C. Rampen, E. Rogers, L. Dudley, and L. Wishart. 2022. "Circular
1049 economy infrastructure: Why we need track and trace for reusable packaging." *Sustain. Prod.*
1050 *Consum.* 29, 249-258.

1051 Franco, N. G., M. F. L. Almeida, and R. F. Calili. 2021. "A strategic measurement framework
1052 to monitor and evaluate circularity performance in organizations from a transition perspective."
1053 *Sustain. Prod. Consum.* 27, 1165-1182.

1054 Giovanardi, M., T. Konstantinou, R. Pollo, and T. Klein. 2023. "Internet of Things for building
1055 façade traceability: A theoretical framework to enable circular economy through life-cycle
1056 information flows." *J. Clean. Prod.* 382, 135261.

1057 Goodall, P., E. Rosamond, and J. Harding. 2014. "A review of the state of the art in tools and
1058 techniques used to evaluate remanufacturing feasibility." *J. Clean. Prod.* 81, 1-15.

1059 Green, S. D., C. C. Kao, and G. D. Larsen. 2010. "Contextualist research: Iterating between
1060 methods while following an empirically grounded approach." *J. Constr. Eng. Manage.* 136(1),
1061 117-126.

1062 Guest, G., E. E. Namey, M.L. Mitchell. 2012. *Collecting qualitative data: A field manual for*
1063 *applied research*. Sage: Thousand Oaks, CA, USA.

1064 Hallowell, M. R. 2012. "Safety-knowledge management in American construction
1065 organizations." *J. Manage. Eng.* 28(2), 203-211.

1066 Henry, M., T. Bauwens, M. Hekkert, and J. Kirchherr. 2020. "A typology of circular start-ups:
1067 An Analysis of 128 circular business models." *J. Clean. Prod.* 245, 118528.

1068 Hossain, M. U., S. T. Ng, P. Antwi-Afari, and B. Amor. 2020. "Circular economy and the
1069 construction industry: Existing trends, challenges and prospective framework for sustainable
1070 construction." *Renew. Sustain. Energy Rev.* 130, 109948.

1071 Housing Authority. 2024. *Number of applications and average waiting time for public rental*
1072 *housing*. Available at: [https://www.housingauthority.gov.hk/en/about-us/publications-and-](https://www.housingauthority.gov.hk/en/about-us/publications-and-statistics/prh-applications-average-waiting-time/)
1073 [statistics/prh-applications-average-waiting-time/](https://www.housingauthority.gov.hk/en/about-us/publications-and-statistics/prh-applications-average-waiting-time/). Accessed on 18 Feb. 2024.

1074 Iacovidou, E., P. Purnell, K. D. Tsavdaridis, and K. Poologanathan. 2021. "Digitally enabled
1075 modular construction for promoting modular components reuse: A UK view." *J. Build. Eng.*
1076 42, 102820.

1077 Johnson, T.R., and J. F. Krems. 2001. "Use of current explanations of multicausal abductive
1078 reasoning." *Cogn. Sci.* 25(6), 903-939.

1079 Jones, M., I. K. Sohn, and A.L. Bendsen. 2017. *Circular procurement case study collection*.
1080 ICLEI – Local Governments for Sustainability, European Secretariat.

1081 IRP. 2018. “Re-defining value – The manufacturing revolution, remanufacturing,
1082 refurbishment, repair and direct reuse in the circular economy.” by N. Nasr, J. Russell, S.
1083 Bringezu, S. Hellweg, B. Hilton, C. Kreiss, and N. von Gries. A Report of the International
1084 Resource Panel. United Nations Environment Programme, Nairobi, Kenya.

1085 Kanters, J. 2018. “Design for deconstruction in the design process: State of the art.” *Buildings*.
1086 8(11), 150.

1087 Kibert, C. J. 2003. “Deconstruction: the start of a sustainable materials strategy for the built
1088 environment.” *Ind. Environ.* 26(2), 84-88.

1089 Kim, S., and S. A. Kim. 2023. “A design support tool based on building information modeling
1090 for design for deconstruction: A graph-based deconstructability assessment approach.” *J.*
1091 *Clean. Prod.* 383, 135343.

1092 Kitayama, S., and O. Iuorio. 2023. “Disassembly and reuse of structural members in steel-
1093 framed buildings: State-of-the-art review of connection systems and future research trends.” *J.*
1094 *Arch. Eng.* 29(4), 03123006.

1095 Krystofik, M., A. Luccitti, K. Parnell, and M. Thurston. 2018. “Adaptive remanufacturing for
1096 multiple lifecycles: A case study in office furniture.” *Resour. Conserv. Recycl.* 135, 14-23.

1097 Lawson, R. M., S. O. Popo-Ola, A. Way, T. Heatley, and R. Pedreschi. 2010. “Durability of
1098 light steel framing in residential applications.” In *Proc., The Institution of Civil Engineers-*
1099 *Construction Materials*. 163(2), 109-121.

1100 Legislative Council Secretariat. 2019. *Fact sheet- transitional housing in selected places*.
1101 Available at: [https://www.legco.gov.hk/research-publications/english/1819fs06-transitional-](https://www.legco.gov.hk/research-publications/english/1819fs06-transitional-housing-in-selected-places-20190218-e.pdf)
1102 [housing-in-selected-places-20190218-e.pdf](https://www.legco.gov.hk/research-publications/english/1819fs06-transitional-housing-in-selected-places-20190218-e.pdf). Accessed on 10 Oct. 2021.

1103 Li, X., W. Lu, F. Xue, L. Wu, R. Zhao, J. Lou, and J. Xu. 2022. "Blockchain-enabled IoT-BIM
1104 platform for supply chain management in modular construction." *J. Constr. Eng. Manage.*
1105 148(2), 04021195.

1106 Ling K. K. 2023. *Study on effective transitional housing delivery in Hong Kong: report on*
1107 *policy recommendations*. Available at: [https://www.polyu.edu.hk/publications/pulse-](https://www.polyu.edu.hk/publications/pulse-polyu/issue/202308/spotlight-on/jcdisi-releases-interim-findings-from-study-on-effective-transitional-housing-delivery-in-hong-kong)
1108 [polyu/issue/202308/spotlight-on/jcdisi-releases-interim-findings-from-study-on-effective-](https://www.polyu.edu.hk/publications/pulse-polyu/issue/202308/spotlight-on/jcdisi-releases-interim-findings-from-study-on-effective-transitional-housing-delivery-in-hong-kong)
1109 [transitional-housing-delivery-in-hong-kong](https://www.polyu.edu.hk/publications/pulse-polyu/issue/202308/spotlight-on/jcdisi-releases-interim-findings-from-study-on-effective-transitional-housing-delivery-in-hong-kong). Accessed on 18 Dec. 2023.

1110 Martinez, J. G., M. Gheisari, and L. F. Alarcón. 2020. UAV integration in current construction
1111 safety planning and monitoring processes: Case study of a high-rise building construction
1112 project in Chile. *J. Manage. Eng.* 36(3), 05020005.

1113 Mayer, M. 2017. "Diversion dynamics: A process-based approach to deconstruction analysis."
1114 In *Proc., 105th ACSA Annual Meeting*. May 2017. ACSA Press.

1115 Minunno, R., T. O'Grady, G. M. Morrison, and R. L. Gruner. 2020. "Exploring environmental
1116 benefits of reuse and recycle practices: A circular economy case study of a modular building."
1117 *Resour. Conserv. Recycl.* 160, 104855.

1118 Munaro, M. R., S. F. Tavares, and L. Bragança. 2022. "The Ecodesign methodologies to
1119 achieve buildings' deconstruction: A review and framework." *Sustain. Prod. Consum.* 30, 566-
1120 583.

1121 Mutikanga, H. E., M. Kayondo, and C. S. Akita. 2023. "Performance of Chinese international
1122 contractors in sub-Saharan Africa: Evidence from Uganda." *J. Manage. Eng.* 39(3), 05023003.

1123 Ottenhaus, L. M., Z. Yan, R. Brandner, P. Leardini, G. Fink, and R. Jockwer. 2023. "Design
1124 for adaptability, disassembly and reuse—A review of reversible timber connection systems."
1125 *Constr. Build. Mater.* 400, 132823.

- 1126 O’Grady, T., R. Minunno, H. Y. Chong, and G. M. Morrison. 2021a. “Design for disassembly,
1127 deconstruction and resilience: A circular economy index for the built environment.” *Resour.*
1128 *Conserv. Recycl.* 175, 105847.
- 1129 O’Grady, T. M., R. Minunno, H. Y. Chong, and G. M. Morrison. 2021b. “Interconnections:
1130 An analysis of disassemblable building connection systems towards a circular economy.”
1131 *Buildings.* 11(11), 535.
- 1132 Oswald, D., and A. Dainty. 2020. “Ethnographic research in the construction industry: a critical
1133 review.” *J. Constr. Eng. Manage.* 146(10), 03120003.
- 1134 Pantini, S., and L. Rigamonti. 2020. “Is selective demolition always a sustainable choice?”
1135 *Waste Manage.* 103, 169-176.
- 1136 Picard, L., P. Blanchet, and A. Bégin-Drolet. 2024. “On-site handling: Automated connecting
1137 device for modular construction used as lifting apparatus.” *Structures.* 63, 106318.
- 1138 Phelps, A. F., and M. J. Horman. 2010. “Ethnographic theory-building research in construction.”
1139 *J. Constr. Eng. Manage.* 136(1), 58-65.
- 1140 Pink, S., D. Tutt, A. Dainty, and A. Gibb. 2010. “Ethnographic methodologies for construction
1141 research: knowing, practice and interventions.” *Build. Res. Inform.* 38(6), 647-659.
- 1142 Proudfoot, K. 2023. “Inductive/deductive hybrid thematic analysis in mixed methods research.”
1143 *J. Mix. Methods Res.* 17(3), 308-326.
- 1144 Rausch, C., M. Nahangi, M. Perreault, C. T. Haas, and J. West. 2017. “Optimum assembly
1145 planning for modular construction components.” *J. Comput. Civ. Eng.* 31(1), 04016039.
- 1146 Roberts, M., S. Allen, J. Clarke, J. Searle, and D. Coley. 2023. “Understanding the global
1147 warming potential of circular design strategies: Life cycle assessment of a design-for-
1148 disassembly building.” *Sustain. Prod. Consum.* 37, 331-343.

1149 Russell, J., and N. Nasr. 2020. "Value retention processes within the circular economy." In:
1150 *Remanufacturing in circular economy*. Nasr, N. (ed.). 2nd edition. Scrivener Publishing,
1151 Beverly, USA.

1152 Russell, J. D., and N. Z. Nasr. 2023. "Value-retained vs. impacts avoided: the differentiated
1153 contributions of remanufacturing, refurbishment, repair, and reuse within a circular economy."
1154 *J. Remanuf.* 13(1), 25-51.

1155 Sanchez, B., and C. Haas. 2018. "A novel selective disassembly sequence planning method for
1156 adaptive reuse of buildings." *J. Clean. Prod.* 183, 998-1010.

1157 Sanchez, B., C. Rausch, and C. Haas. 2019. "Deconstruction programming for adaptive reuse
1158 of buildings." *Auto. Constr.* 107, 102921.

1159 Santos, A., and J. de Brito. 2007. "Building deconstruction in Portugal: a case study." In *Proc.,*
1160 *Portugal SB07 Conference—sustainable construction, materials and practices—challenge of*
1161 *the industry for the new millennium*. 1059-1066.

1162 Schultmann, F. 2005. "Sustainable deconstruction of buildings." *Smart Sustain. Built Environ.*
1163 148-159.

1164 Seike, T., Y. Kim, Y. Hosaka, S. Ida, and T. Masuda 2018. "Intraregional reuse of emergency
1165 temporary housing in Japan." *Sustain. Cities Soc.* 42, 650-662.

1166 Smith, S., and P. Y. Hung. 2015. "A novel selective parallel disassembly planning method for
1167 green design." *J. Eng. Design.* 26(10-12), 283-301.

1168 Spearing, L. A., A. Bakchan, L. C. Hamlet, K. K. Stephens, J. A. Kaminsky, and K. M. Faust.
1169 2022. "Comparing qualitative analysis techniques for construction engineering and
1170 management research: The case of Arctic water infrastructure." *J. Constr. Eng. Manage.* 148(7),
1171 04022058.

1172 Tan, T., G. Mills, J. Hu, and E. Papadonikolaki. 2021. "Integrated approaches to design for
1173 manufacture and assembly: A case study of Huoshenshan hospital to combat COVID-19 in
1174 Wuhan, China." *J. Manage. Eng.* 37(6), 05021007.

1175 Tan, T., G. Mills, and E. Papadonikolaki. 2024. "Exploring multidimensional modularity:
1176 Strategies to reduce complexity in design activities." *J. Manage. Eng.* 40(3), 05024002.

1177 Tatiya, A., D. Zhao, M. Syal, G. H. Berghorn, and R. LaMore. 2018. "Cost prediction model
1178 for building deconstruction in urban areas." *J. Clean. Prod.* 195, 1572-1580.

1179 Tavory, I., and S. Timmermans. 2014. *Abductive analysis: Theorizing qualitative research*.
1180 University of Chicago Press.

1181 Thompson, J. 2022. "A guide to abductive thematic analysis." *Qual. Report.* 27(5), 1410-1421.

1182 UNECE (United Nations Economic Commission for Europe). 2021. *Housing for migrants and
1183 refugees in the UNECE region challenges and practices*.

1184 van den Berg, M., H. Voordijk, and A. Adriaanse. 2020. "Recovering building elements for
1185 reuse (or not)—Ethnographic insights into selective demolition practices". *J. Clean. Prod.* 256,
1186 120332.

1187 van Stijn, A., L. M. Eberhardt, B. W. Jansen, and A. Meijer. 2021. "A circular economy life
1188 cycle assessment (CE-LCA) model for building components." *Resour. Conserv. Recycl.* 174,
1189 105683.

1190 Xu, X., and H. Yang. 2020. "Vision measurement of tunnel structures with robust modelling
1191 and deep learning algorithms." *Sensors.* 20(17), 4945.

1192 Yeum, C. M., and S. J. Dyke. 2015. "Vision-based automated crack detection for bridge
1193 inspection." *Comput.-Aided Civ. Infrastruct. Eng.* 30(10), 759-770.

- 1194 Yang, Y., J. Guan, J. M. Nwaogu, A. P. Chan, H. L. Chi, and C. W. Luk. 2022. "Attaining
1195 higher levels of circularity in construction: Scientometric review and cross-industry
1196 exploration." *J. Clean. Prod.* 375, 133934.
- 1197 Yang, Y., B. Zheng, C. Luk, K. F. Yuen, and A. Chan. 2024. "Towards a sustainable circular
1198 economy: Understanding the environmental credits and loads of reusing modular building
1199 components from a multi-use cycle perspective." *Sustain. Prod. Consum.* 46, 543-558.
- 1200 Yin, R. K. 2017. *Case study research and applications: Design and methods*. Thousand Oaks,
1201 CA: SAGE
- 1202 Yu, Y., D. M. Yazan, V. Junjan, and M. E. Jacob. 2022. "Circular economy in the construction
1203 industry: A review of decision support tools based on Information & Communication
1204 Technologies." *J. Clean. Prod.* 349, 131335.
- 1205 Zhai, Y., K. Chen, J. X. Zhou, J. Cao, Z. Lyu, X. Jin, G.Q.P. Shen, W. Lu, G. Q. Huang. 2019.
1206 "An Internet of Things-enabled BIM platform for modular integrated construction: A case
1207 study in Hong Kong." *Adv. Eng. Inform.* 42, 100997.
- 1208 Zhang, C., M. Hu, F. Di Maio, B. Sprecher, X. Yang, and A. Tukker. 2022. "An overview of
1209 the waste hierarchy framework for analyzing the circularity in construction and demolition
1210 waste management in Europe." *Sci. Total Environ.* 803, 149892.

1211 Fig. 1. Research framework

1212 Fig. 2. Schematic diagram of the modular building Note: The BIM was developed by the
1213 authors based on the 2D drawings shared by the interviewees

1214 Fig. 3. Design of bolts and nuts connection Note: The 3D connection configuration was
1215 produced by the authors based on the 2D and 3D drawings shared by the interviewees

1216 Fig. 4. Disconnection of inter-module joints Note: The 3D disconnection configuration was
1217 produced by the authors based on the 2D and 3D drawings shared by the interviewees

1218 Fig. 5. Connection of inter-module joints Note: The 3D connection configuration was produced
1219 by the authors based on the 2D and 3D drawings shared by the interviewees

1220 Fig. 6. The disassembly sequence (adapted from Construction Industry Council 2023)

1221 Note: Each of 68 modular units was assigned with a unique label. For each label, the first
1222 character represents the story, the second character represents the zone, and the third character
1223 represents the sequential number of each modular unit per floor

Table 1. Key findings of the case study

Deconstruction process	Deconstruction sub-process	Key findings	Sources
Disassembly	Disconnecting joints	Bolts and nuts disconnection but lock-in stress requires manual handling	Site observation, interview, archival research
	Disassembly of modules	Hybrid sequential and parallel disassembly sequence	Site observation, interview, archival research
Reverse logistics	Take-back mechanism	Client ownership, Novel take-back mechanism	Interview
	Traceability	QR code used to track modular units, Tracible disassembly and reuse processes but limitations are observed	Site observation
Value retention	Quality inspection	Three-stage quality inspection before and after disassembly and before reassembly	Site observation, archival research
	Touch-ups	Removing rust stains and applying protective zinc coating and fireproofing coating on the affected connections and steel members, Replacing deteriorated fire sealants and gemtree boards, Replacing deteriorated wall and floor tiles	Site observation, interview, archival research